BRUHAT BANAGLORE MAHANAGARA PALIKE

EXTRA ITEM RATE LIST

Name of Work:Repair and Maintenance of Footpaths in Someshwara Ward no-03 of Yalahanka Satellite town Sub Division

Job Code :

Agency: Sri.Manoj Naik B M

Sl No	Item Of Work	Unit	Estimate qty	Rate	Amount (Rs.)	Whether the item alternative in tender or additional items	item is included in sanctioned estimate	How the Cost is proposed to be met	Whether extra item is included in S.R.	Remarks
1	2	3	4	5	6	7	8	9	10	11
E1	Removing and resetting of FootPath Slab	M	772.38	219.49	169530.00	Additonal Item	No	Savings in Estimate	Data mte	
E2	Earth work excavation by manual means for drains,canals, waste weir, draft, approach channels, key trenches, foundation of bridges and such simillar works in all kinds of soils , as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, removal of stumps and other deleterious matter, excavated surface leveled and sides neatly dressed disposing off the excavated stuff or sorting & stacking the selected stuff for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools & other appurtenaces required to complete the work	Cum	362.10	191.10	69196.00	Additonal Item	No	Savings in Estimate	Yes	

Cost of tender form in Rs. (non-refundable) : As per SI
Procurement Portal
Dates of Events: (1) Tenders must be submitted online
17.30hrs (During office Hours)
Further details on date of opening the Tender/Detail of work E.M.D.

E3	Providing and constructing un-reinforced plain cement concrete pavement, thickness as per design, over a prepared sub base, with 43 grade cement or any other type as per Clause 1501.2.2 M30 (Grade), coarse and fine aggregates conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm, mixed in a concrete mixer of not less than 0.2 cum capacity and appropriate weigh batcher using approved mix design, laid in approved fixed side formwork (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including levelling the formwork as per drawing), spreading the concrete with shovels, rakes, compacted using needle, screed and plate vibrators and finished in continuous operation including construction joints, , primer, sealant , curing of concrete slabs for 14- days, and water finishing to lines and grade as per drawing and technical specification clause 1501 with all lead, lifts, loading & unloading charges, cost and conveyance of all materials, labour, equipments etc., complete MORTH Specification No.1501 as per the directions of the Engineer-in-charge of the work. (PWD SR	Cum	17.33	6690.43	115912.00	Additional Item	No	Savings in Estimate	Yes	
	TOTAL EIRL AMOUNT				**354638.00**						
	AMOUNT IN WORDS	**Three Lakhs Fifty Four Thousand Six Hundred Thirty Eight rupees**									

PERCENTAGE OF EXCESS OVER AMOUNT PUT TO TENDER

EIRL Amount = **354638.00** x100 = **14.93** %

Approved Tender Price **2374545.00**

Asst Engineer

Asst.Executive Engineer

Executive Engineer